



Freshkills Park

Near-Term Park Construction Projects

Schmul Park




Schmul Park




Schmul Park



Owl Hollow Comfort Station



Owl Hollow Comfort Station



Road System



Road System: Objectives

- **Provide access to Park**
- Provide Park-like experience for drivers
- Connectivity to local/regional network
- Minimize or avoid impacts with landfill infrastructure and protected natural features



Road System: Objectives

- Provide access to Park
- **Provide Park-like experience for drivers**
- Connectivity to local/regional network
- Minimize or avoid impacts with landfill infrastructure and protected natural features


Rendering of possible 2-lane option




2-lane, 4-lane and hybrid system still being analyzed

Road System: Objectives

- Provide access to Park
- Provide Park-like experience for drivers
- **Connectivity to local/regional network**
- Minimize or avoid impacts with landfill infrastructure and protected natural features






Road System: Objectives

- Provide access to Park
- Provide Park-like experience for drivers
- Connectivity to local/regional network
- **Avoid or minimize impacts with landfill infrastructure and protected natural features**



Technical Constraints

CRITICAL SITE FEATURES



West Shore Expressway

Landfill
Section 3/4

Landfill
Section 6/7

Landfill
Section 2/8

Landfill
Section 1/9

Richmond Hill
Road

Forest Hill
Road

Arden Heights
Woods

Arden Heights

William T. Davis
Wildlife Refuge

New
Jersey


Travis

Staten
Island
Mall

La Tourette Park

Arthur Kuf Road

The site is dominated by wetlands and landfill infrastructure



Wetland Systems

Tidal Wetland
Freshwater Wetlands

EAST MOUND

Richmond Hill Road

Tidal Wetlands

Freshwater
Wetlands

Forest Hill Road



Landfill Systems

Leachate Management
Landfill Gas Management
Final Cover + Drainage Systems

Landfill Systems

Leachate Management


Landfill Gas Management

Final Cover + Drainage Systems

LEACHATE MANAGEMENT SYSTEM

- Containment
 - Cutoff Wall
- Collection
 - Leachate Collection Drain
- Conveyance
 - Leachate Collection Pump Stations
 - Leachate Force Main


LEACHATE MANAGEMENT SYSTEM



LEACHATE MANAGEMENT SYSTEM

Containment

Typical Cross Section FKL
(Section 1/9, 6/7)




Typical Cutoff Wall
Construction



LEACHATE MANAGEMENT SYSTEM

Collection - Conveyance

Typical Cross Section FKL
(Section 1/9, 6/7)




Leachate Collection Drain
Construction



- **Collection Drain** - Stone backfill with perforated pipe
- Gravity drainage to **Leachate Collection Pump Station**
- Pump stations - 6 ft x 12 ft plastic lined concrete vault
- Pressure flow through **Leachate Collection Header**

LEACHATE MANAGEMENT SYSTEM

Typical Cross Section FKL
(Section 1/9, 6/7)



• Constraints


- Road construction must **NOT** compromise the integrity of the Leachate Management System
- Cutoff Wall and Collection Drain are permanent features
- Cannot bury Leachate Collection Pump Stations

• Mitigation Measures

- Demonstrate acceptability of the design
- Analyze slope stability
- Monitor Cutoff Wall for movement

LEACHATE MANAGEMENT SYSTEM

Cannot Bury Leachate Collection Pump Stations



Landfill Systems

Leachate Management

Landfill Gas Management

Final Cover + Drainage Systems


LANDFILL GAS (LFG) MANAGEMENT SYSTEM

- Gas Collection
 - LFG Extraction Wells
 - LFG Flare Stations
- Gas Migration
 - LFG Interceptor Venting System
 - LFG Migration Monitoring Wells


LANDFILL GAS MANAGEMENT SYSTEM

LFG Gas Collection

Typical LFG Collection Components




Typical LFG Extraction Well Head



LANDFILL GAS MANAGEMENT SYSTEM

LFG Collection

Typical LFG Collection Components



- **Constraints**

- Road construction must **NOT** compromise the integrity of the LFG Management System
- Cannot bury access to Condensate Tanks

- **Mitigation Measures**

- Demonstrate acceptability of the design
- Strategic abandonment and relocation of LFG Extraction Wells, or LFG Header Pipes
- Provide structural reinforcement to LFG Header Pipes

LANDFILL GAS MANAGEMENT SYSTEM

LFG Collection

FKLF Section 6/7 LFG Flare Station



- **Constraints**

- LFG Flare Stations are permanent structures
- Multiple utility connections points (firewater, LFG header pipe, condensate tanks, electricity)
- Must maintain vehicle access
- Provide crash protection, as necessary


- **Mitigation Measures**

- Road alignment should avoid LFG Flare Stations

LANDFILL GAS MANAGEMENT SYSTEM

LFG Migration Control

Typical LFG Migration Components




- **LFG Interceptor Venting System** – Trench with stone backfill. Extends to groundwater of low permeability soil layer
- **LFG Utility Seal** – Low permeability soil-cement backfill to prevent gas migration
- **LFG Migration Monitoring Well** – Quarterly Inspection required

LANDFILL GAS MANAGEMENT SYSTEM

LFG Migration Control

Typical LFG Migration Components



- **Constraints**

- Road construction must **NOT** compromise the integrity of the LFG Management System

- **Mitigation Measures**

- Demonstrate acceptability of the design
- Reconstruct LFG Interceptor Venting System and/or LFG Migration Monitoring Wells
- Augment venting system with lateral vent layer

Landfill Systems

Leachate Management

Landfill Gas Management

Final Cover + Drainage Systems


FINAL COVER & DRAINAGE SYSTEM

- Waste Containment
 - Multi-Layered Soil/Aggregate and Geosynthetic Cover System
- Stormwater Management
 - Swales
 - Culverts
 - Downchutes
 - Drop Inlets
 - Basins and Outfalls

FINAL COVER & DRAINAGE SYSTEM

Waste Containment

Typical Final Cover System Components




- **Topsoil & Vegetative Layer** – Promote vegetation for resistance to soil erosion
- **Barrier Protection Material** – Physical separation and protection of underlying geosynthetic materials
- **Drainage Layer** – Release infiltration water
- **Hydraulic Barrier Layer** – Reduce infiltration and leachate generation
- **Gas Venting Layer** – Dissipate LFG pressure

FINAL COVER & DRAINAGE SYSTEM

Waste Containment

Typical Final Cover System Components




Five (5) Different Final Cover Systems Approved for Landfill Section 6/7

- **Vegetated Area Final Cover**
 - (1) Slopes 4 to 15 percent
 - (2) Slopes 15 to 33 percent
- **Driving Surfaces Final Cover**
 - (3) Asphalt Roads
 - (4) Gravel Roads
- **Perimeter Cutoff Wall**
 - (5) Soil or Asphalt

FINAL COVER & DRAINAGE SYSTEM

Waste Containment

Typical Final Cover System Components




Five (5) Different Final Cover Systems Approved for Landfill Section 6/7

- **Vegetated Area Final Cover**
 - (1) Slopes 4 to 15 percent
 - (2) Slopes 15 to 33 percent
- **Driving Surfaces Final Cover**
 - (3) Asphalt Roads
 - (4) Gravel Roads
- **Perimeter Cutoff Wall**
 - (5) Soil or Asphalt

FINAL COVER & DRAINAGE SYSTEM

Waste Containment

Typical Final Cover System Components




Five (5) Different Final Cover Systems Approved for Landfill Section 6/7

- **Vegetated Area Final Cover**
 - (1) Slopes 4 to 15 percent
 - (2) Slopes 15 to 33 percent
- **Driving Surfaces Final Cover**
 - (3) Asphalt Roads
 - (4) Gravel Roads
- **Perimeter Cutoff Wall**
 - (5) Soil or Asphalt

FINAL COVER & DRAINAGE SYSTEM


Waste Containment




- **Constraints**
 - Road construction must **NOT** compromise the integrity of the Final Cover System
- **Mitigation Measures**
 - Monitor geosynthetic layer for settlement
 - Analyze for stability

FINAL COVER & DRAINAGE SYSTEM

Stormwater Management System - Downchutes



FINAL COVER & DRAINAGE SYSTEM



- **Constraints**

- Some downchutes connect to fixed discharge points connected to the Cutoff wall

- **Mitigation Measures**


- Road alignment should avoid disturbing drop inlet locations

LANDFILL SYSTEMS / ROAD DESIGN INTERACTION

- Leachate Management
 - Not easily modified.
 - Demonstration/monitoring likely required.
- Landfill Gas Management
 - More easily modified.
 - Temporary by-pass options exist.
- Final Cover & Drainage Systems
 - Multiple cover system concepts established.
 - Demonstration and monitoring likely required.



Freshkills Park Roads



LEGEND

- OFF-LANDFILL ALIGNMENT
- ON-SERVICE ROAD ALIGNMENT
- ON-LANDFILL ALIGNMENT

EAST MOUND
ALIGNMENT OPTIONS



East Mound Alignments

Three Corridors

Western

Eastern

Southern


Each With Three Placements


Off-Landfill

On-Service Road

On-Landfill

Western Corridor





OFF-LANDFILL

- Tidal wetlands

(difficult)

ON-SERVICE ROAD

- Leachate pump stations
- Leachate cutoff wall
- Operations and Maintenance


(difficult)


ON-LANDFILL

- Excessive fill
- Stability
- Long-term settlement
- Crossing leachate cutoff wall

(difficult)

Eastern Corridor





ON-LANDFILL

- Excessive fill
- Stability
- Long-term settlement
- Stormwater downchute

(difficult)

ON-SERVICE ROAD

- Leachate pump stations
- Stormwater downchute
- Operations and Maintenance


(difficult)


OFF-LANDFILL

- Fresh water wetlands
- Crossing leachate cutoff wall
- Stormwater basin

(less difficult)

Southern Corridor





ON-LANDFILL

- Landfill gas header and wells
- Crossing leachate cutoff wall

(less difficult)

ON-SERVICE ROAD


- Leachate pump stations
- Crossing leachate cutoff wall
- Operations and Maintenance

(difficult)

OFF-LANDFILL


- Tidal wetlands
- Stormwater basin


(difficult)



RECOMMENDED PARK ROADS

Proposed West Shore Expressway Improvements






Traffic Analysis

Overview of the EIS Traffic Impact Analysis

EIS Traffic Chapter will address these technical areas:

- Traffic flow and operating conditions for the existing, future No-Build and proposed project (Build)
- Assessment of the impact of traffic diversions from park roads
- Coordination with planning and design efforts to ensure adequate park access and traffic circulation
- Maximization of operations and presentation of mitigation/improvement measures


Intersections Under Analysis



- Project Site Boundary
- Primary Study Area Intersection
- Secondary Study Area Intersection
- ATR Count Locations


0 1000 2000 FEET
SCALE

FRESH KILLS PARK GEIS TRAFFIC ANALYSIS FRAMEWORK



FRESH KILLS PARK GEIS

TRAFFIC ANALYSIS FRAMEWORK (continued)



Roadway Improvement Projects Planned for the Area


New York City Department of Transportation (NYCDOT)

- Arthur Kill Road Improvement Project
- Victory Boulevard and Travis Avenue Intersection Design
- Richmond Hill Road Study
- Forest Hill Road Improvement Project
- Richmondtown Roadway Improvement Study
- Rockland Avenue and Manor Road Improvement Project
- Woodrow Road Improvement Project
- Bloomingdale Road Improvement Project
- Arden Avenue/Amboy Road Intersection Improvement Project


New York State Department of Transportation (NYSDOT)

- Korean War Veterans Parkway Ramp
- West Shore Expressway Improvements
- Arthur Kill Road Park and Ride Facility

2016
Park Roads



2.6.08



Next Steps

- Complete traffic modeling and analysis
- Review and coordinate Traffic Impact Analysis with NYCDOT and NYSDOT
- Conduct CORSIM Analysis for West Shore Expressway segment
- Identify Mitigation/Improvement Measures
- Complete Draft Generic EIS and begin public review process



Freshkills Park